BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED

SECTION- IX

VOLUME-II

Bill of Quantities (BOQ)

PART-I SUPPLY PORTION				
SL No	**Particulars**	**Unit**	**Total Qty**	**Material Code**
1	Supply & Erection of PSCC pole 9 mtr long 300 kg W/L (for dead end and anchor points only)	No	**10**	200005
2	Supply & Erection of PSCC pole 9 mtr long 200kg W/L (for intermediate only)	No	**90**	200006
3	Supply & Erection of 11 kV, Horizontal Cross Arm with clamps, HTST supports, bolts, nuts and washers for PSCC Pole - 9 Mtr Long, 200 Kg WL-GI	set	**120**	CDS materials for General works
4	Supply & Providing of 45KN Composite polymer insulators.	No	**72**	283320
5	Supply & Providing of 11kV Composite Polymer pins insulators.(24mm dia FRP rod)	No	**312**	283008
6	Supply & Providing of Guy Set Complete with No. 15 Strain Insulator & Concreting materials-GI	set	**28**	CDS materials for General works
7	Supply & stringing of ACSR Rabbit conductor with 1.5% sag as per BESCOM Specification	Km	**19.285**	284108
8	Supply & Providing of Spiral Earth Electrode	No	**120**	281683
9	Supply & erection of DP set (2 pole structure kit- GI) with 9 mtr PSCC, 300 KG W/L including 5Kg , 8SWG GI wire for structure grounding.	set	**5**	CDS 46
10	Supply & providing of 11kV class 200 AMPS Single Break GOS	Set	**9**	304212
11	Supply & providing of H - Frame Set for 11kV, 200Amps Single Break GOS Mounting - GI	Set	**5**	280149
12	Supply & providing of 11kV Spl 3pin X-arms, pole clamps, bolts for PSCC pole- GI	No	**10**	280013
13	Supply & providing of 11kV Class DOLO Cutouts	Set (3 Nos)	**5**	302011
14	Supply & providing of caution/Danger board as per drawing no.BESCOM/GM/CP/40/24.10.17	No	**14**	613050
15	Supply & Fixing of Anticlimbing Device GI Barbed Wire (12 mtrs/1kg)Lumpsum	Kg	**248**	278911
16	Supply & Erection of Double Pole Mounted Transformer kit for 63 kVA with 2 Nos of 9 mtr long PSCC Pole, 300KG W/L- GI	Set	**2**	281674+600095+607054, CDS 60
17	Supply & Erection of 11kV/433V, 63 kVA,3phase 50cys Distribution Transformer BEE-4star rated	No	**2**	281008
18	Supply & providing of Earthing materials pipe type for grounding as per Drawing No BESCOM/GM/CP/15&34 dt:24.10.17(Single Electrode with accessories)	No	**12**	281110
19	Supply & providing of GI wire 8SWG	kg	**20**	303202, CDS

				60
20	Supply & providing of Guy wire 7/10SWG	kg	**40**	301107
21	Supply & providing of 11kV lightning arrestors, poliymer Type,9kV 5 kA (Set=3No)	Set	**4**	
22	Supply & providing of LT Protection kit	No	**4**	289031
23	Supply & providing of LT wiring (from 63 KVA DTC to LT line)		**2**	288531
	i) Al Lead Wire - 95 Sqmm	Mtr	**60**	285508, CDS 60
	ii) Heavy Duty Long Barrel Copper Lug - 95 Sqmm	No	**16**	284503
	iii) PG Clamp - Rabbit to 95 Sqmm	No	**8**	280800+280511, CDS 60
	iv) Spacer for DTC Wiring	No	**8**	CDS 39
	v) Fish Plate with necessary Clamps, bolts & nuts etc complete (Galvanised)	No	**16**	302122
	vi) LT Metering box with CTs and necessary wiring for housing ETV Meter (Please see CDS - 39)	No	**0**	613050
24	Supply & providing of H.G.Fuse unit,11kV solid core Type(Set=3no)	Set	**4**	278911
25	supply & providing Transparent Alkathine tube 19mm dia, 2mm thick in coils of 30 mtrs	Coil	**4**	200005
26	Supply & Erection of 9M PSCC pole WL 300Kg	No	**2**	280119, CDS materials for General works
27	Supply & Erection of Single Pole Mounted Transformer kit for 25 kVA on 9 mtr PSCC Poles of 300kG WL --GI with H-frame	Set	**2**	281110
28	Supply & Erection of 11kV/433V, 25 kVA,3phase 50cys Distribution Transformer BEE-4star rated	No	**2**	303202, CDS 60
29	Supply & providing of LT wiring (from 25 KVA DTC to LT line)		**2**	280800+280511, CDS 63
a	Aluminium lead wire 50 sqmm	Mtr	**50**	284503
b	Heavy duty long barrel copper lugs- 50 sqmm	No	**16**	CDS 39
c	P.G Clamps - Rabbit to 50 sq.mm	No	**8**	302122
d	Fish Plate with necessary Clamps, bolts & nuts etc complete (Galvanised)	No	**8**	613050
e	Spacers for DTC wiring	No	**16**	278911
30	PSCC Pole - 8 Mtr Long, 200 Kg WL (for Intermediate Pole)	No	**20**	284108
31	LT 4 Pin Cross Arm with clamps, bolts, nuts and washers for PSCC Pole - 8 Mtr Long, 200 Kg WL-GI	Set	**20**	CDS 69
32	1.1 kV Pin Insulator with GI Pin	No	**80**	0
33	No. 8 Strain Insulator	No	**8**	CDS 69
34	Supply & Providing of Guy Set Complete with No 8. Strain Insulator & Concreting materials-GI	Set	**4**	CDS 69

PART-II ERECTION PORTION			
SL No	**Particulars**	**Unit**	**Total Qty**
1	Supply & Erection of PSCC pole 9 mtr long 300 kg W/L (for dead end and anchor points only)	No	**10**
2	Supply & Erection of PSCC pole 9 mtr long 200kg W/L (for intermediate only)	No	**90**
3	Supply & Erection of 11 kV, Horizontal Cross Arm with clamps, HTST supports, bolts, nuts and washers for PSCC Pole - 9 Mtr Long, 200 Kg WL-GI	set	**120**
6	Supply & Providing of Guy Set Complete with No. 15 Strain Insulator & Concreting materials-GI	set	**28**
7	Supply & stringing of ACSR Rabbit conductor with 1.5% sag as per BESCOM Specification	Km	**19.285**
8	Supply & Providing of Spiral Earth Electrode	No	**120**
9	Supply & erection of DP set (2 pole structure kit- GI) with 9 mtr PSCC, 300 KG W/L including 5Kg , 8SWG GI wire for structure grounding.	set	**5**
10	Supply & providing of 11kV class 200 AMPS Single Break GOS	Set	**9**
11	Supply & providing of H - Frame Set for 11kV, 200Amps Single Break GOS Mounting - GI	Set	**5**
12	Supply & providing of 11kV Spl 3pin X-arms, pole clamps, bolts for PSCC pole- GI	No	**10**
13	Supply & providing of 11kV Class DOLO Cutouts	Set (3 Nos)	**5**
15	Supply & providing of caution/Danger board as per drawing no.BESCOM/GM/CP/40/24.10.17	No	**14**
16	Supply & Fixing of Anticlimbing Device GI Barbed Wire (12 mtrs/1kg)Lumpsum	Kg	**248**
17	Supply & Erection of Double Pole Mounted Transformer kit for 63 kVA with 2 Nos of 9 mtr long PSCC Pole, 300KG W/L- GI	Set	**2**
18	Supply & Erection of 11kV/433V, 63 kVA,3phase 50cys Distribution Transformer BEE-4star rated	No	**2**
19	Supply & providing of Earthing materials pipe type for grounding as per Drawing No BESCOM/GM/CP/15&34 dt:24.10.17(Single Electrode with accessories)	No	**12**
20	Supply & providing of 11kV lightning arrestors, poliymer Type,9kV 5 kA (Set=3No)	Set	**4**
21	Supply & providing of LT Protection kit	No	**4**

22	Supply & providing of LT wiring (from 63 KVA DTC to LT line)		**2**
	i) Al Lead Wire - 95 Sqmm	Mtr	**60**
	ii) Heavy Duty Long Barrel Copper Lug - 95 Sqmm	No	**16**
	iii) PG Clamp - Rabbit to 95 Sqmm	No	**8**
	iv) Spacer for DTC Wiring	No	**8**
	v) Fish Plate with necessary Clamps, bolts & nuts etc complete (Galvanised)	No	**16**
	vi) LT Metering box with CTs and necessary wiring for housing ETV Meter (Please see CDS - 39)	No	**0**
23	Supply & providing of H.G.Fuse unit,11kV solid core Type(Set=3no)	Set	**4**
24	Supply & Erection of 9M PSCC pole WL 300Kg	No	**2**
25	Supply & Erection of Single Pole Mounted Transformer kit for 25 kVA on 9 mtr PSCC Poles of 300kG WL --GI with H-frame	Set	**2**
26	Supply & Erection of 11kV/433V, 25 kVA,3phase 50cys Distribution Transformer BEE-4star rated	No	**2**
27	Supply & providing of LT wiring (from 25 KVA DTC to LT line)		**2**
a	Aluminium lead wire 50 sqmm	Mtr	**50**
b	Heavy duty long barrel copper lugs- 50 sqmm	No	**16**
c	P.G Clamps - Rabbit to 50 sq.mm	No	**8**
d	Fish Plate with necessary Clamps, bolts & nuts etc complete (Galvanised)	No	**8**
e	Spacers for DTC wiring	No	**16**
f	LT Metering box with CTs and necessary wiring for housing ETV Meter (Please see CDS - 39)	No	**0**
28	PSCC Pole - 8 Mtr Long, 200 Kg WL (for Intermediate Pole)	No	**20**
29	LT 4 Pin Cross Arm with clamps, bolts, nuts and washers for PSCC Pole - 8 Mtr Long, 200 Kg WL-GI	Set	**20**
30	Supply & Providing of Guy Set Complete with No 8. Strain Insulator & Concreting materials-GI	Set	**4**
31	Guy concreting with Boulders, Mud and Sand	No	**4**